

compose.kerala.gov.in
egazette.kerala.gov.in
printing.kerala.gov.in



Regn.No. KERBIL/2012/45073
dated 2012-09-05 with RNI
Reg No.KL/TV(N)/634/2021-2023

കേരള സർക്കാർ
GOVERNMENT OF KERALA

കേരള ഗസറ്റ് KERALA GAZETTE

ആധികാരികമായി പ്രസിദ്ധപ്പെടുത്തുന്നത്
PUBLISHED BY AUTHORITY

ചൊവ്വ, 2024 ഫെബ്രുവരി 27
Tuesday, 27th February 2024

1199 കുംഭം 14
14th Kumbham 1199

വാല്യം 13
Vol. XIII

1945 ഫാൽഗുനം 8
8th Phalguna 1945

നമ്പർ } 9
No. }

Part III

Collegiate Education Department

©
കേരള സർക്കാർ
GOVERNMENT OF KERALA
2024



ദർഘാസ് പരസ്യം

നമ്പർ: A3/856/2023/CSMGCCLKDY

തീയതി: 21.02.2024

ശ്രീ സി അച്യുത മേനോൻ സർക്കാർ കോളേജിലേക്ക് 2023-24 അധ്യയന വർഷത്തിലേക്ക് സ്റ്റാറ്റിസ്റ്റിക്സ് ഡിപ്പാർട്ട്മെന്റിലെ കമ്പ്യൂട്ടർ ലാബ് നെറ്റ്വർക്ക് ചെയ്യുന്നതിന് തയ്യാറുള്ള വ്യക്തികൾ/സ്ഥാപനങ്ങൾ എന്നിവരിൽ നിന്നും മുദ്ര വച്ച ദർഘാസുകൾ ക്ഷണിച്ചുകൊള്ളുന്നു.

അടങ്കൽ തുക - 2,10,500/- രൂപ

ലാബ് നെറ്റ്വർക്ക് ചെയ്യുന്നത് സംബന്ധിച്ച വിവരങ്ങൾ താഴെ ചേർക്കുന്നു.

Sl.No.	Item Description	Quantity
1	Network	
1.01	Managable switch 48 port Gigabit -Supply, installation, fluke testing and commissioning of 1U high, 48-port Gigabit switch maximizes bandwidth and density for great value and capability. With 48 10/100/1000 Mbps ports, each capable of powering 2000 Mbps of data throughout in full-duplex mode, plus four optional fiber ports, it provides a 40 Gbps backbone and connects servers or power users, delivering large amounts of multimedia, image and video information in no time at all. Standards-based, it is ideal for combining 10, 100, and 1000 Mbps devices, as it delivers automatic speed and full/half-duplex sensing plus Auto Uplink™ on every port. Four hot-swappable Small Form-factor Pluggable (SFP)** GBIC slots provide optional fiber connectivity for greater distance. An intuitive, web-browser interface offers simple switch management, making it a snap to monitor switch performance, configure ports, even set up trunks, VLANs, and prioritization.	1 Nos
1.02	Information Outlet RJ 45 - Supply, fixing, fluke testing and commissioning of CAT 6 Information Outlets (Key stone) with Shuttered Faceplate, Single port, white, jack, suitable PVC / GI Modular Box etc. including necessary connections with all accessories required for complete installation.	36 Nos
1.03	CAT6 Cable - Supplying and drawing of Category 6 cable consists of 4 pairs of solid insulated copper 23AWG, surface/ recessed PVC conduit through wall/tray with all accessories as required for complete installation and making good all damages made for installation.	600 Mtrs



1.04	OFC Cable - Supplying and drawing of 6 core un-armoured Optical Fibre Cable (OFC) through wall/tray with all accessories as required for complete installation(From main block BBA lab to Science Block, Approximately 400Mtrs , Through Underground)	400 Mtrs
1.05	Patch cable - Supply, fixing, testing and commissioning of CAT6 Patch Cable - 1 Meter length etc. of approved make as required for complete installation.	36 Nos
2	Active Components, Racks & Accessories	
2.01	Supply, Installation, Testing and installation of Cat - 6, 24 port fully loaded patch panel with necessary cable manager for routing the cable inside rack with all accessories required for complete installation as required as directed by the engineer in charge	2 Nos
2.02	Cable manager	4 Nos
2.03	9U Rack	1 Nos
3	Installation Testing & Commissioning	
3.01	Installation, Testing & Commissioning charges, if any	1 Nos

കവറിനു പുറത്ത് " TENDER NUMBER, FOR THE WORK OF STATISTICS LAB NETWORKING " എന്ന് രേഖപ്പെടുത്തേണ്ടതാണ്. ദർഘാസ് ഫോറത്തിൽ ഉത്തരവാദിപ്പെട്ട ഉദ്യോഗസ്ഥന്റെ ഒപ്പ് രേഖപ്പെടുത്തേണ്ടതാണ്. ദർഘാസ് ഫോറത്തോടൊപ്പം 200/- രൂപ മുദ്രപത്രത്തിൽ പ്രാഥമിക ഉടമ്പടി സമർപ്പിക്കേണ്ടതാണ്. രേഖപ്പെടുത്തുന്ന വിലയുടെ ഒരു ശതമാനം (1%) നിതരദ്രവ്യ നിക്ഷേപമായി (EMD) ഒടുക്കേണ്ടതാണ്. ഈ തുക ഡിമാന്റ് ഡ്രാഫ്റ്റായി താഴെ ഒപ്പിട്ടിരിക്കുന്ന ഉദ്യോഗസ്ഥന്റെ പേർക്ക് നൽകേണ്ടതാണ്.

ദർഘാസ് ഫോറങ്ങൾ ഈ ഓഫീസിൽ എല്ലാ പ്രവർത്തി ദിവസങ്ങളിലും കാലത്ത് 10 മണി മുതൽ ഉച്ചക്ക് 2 മണി വരെ ലഭ്യമാണ്. മേൽപ്പറഞ്ഞ വ്യവസ്ഥകൾ പാലിക്കാത്ത ടെൻഡറുകൾ നിരസിക്കുന്നതാണ്. ടെൻഡറിൽ പങ്കെടുക്കാനാഗ്രഹിക്കുന്നവർ ടെൻഡർ ഫോറത്തിന്റെ വില നേരിട്ടോ, ഓൺലൈൻ മുഖേനയോ അടക്കേണ്ടതാണ്. ടെൻഡർ ഫോറത്തിന്റെ വില മടക്കി നൽകുന്നതല്ല. ടെൻഡർ ഫോറം തപാൽ മാർഗ്ഗം ലഭിക്കുന്നതിനു ടെൻഡർ ഫോറത്തിന്റെ വിലയും രജിസ്ട്രേഡ് ചാർജ്ജുമടക്കം മണി ഓർഡറായി അയച്ചു നൽകേണ്ടതാണ്.

ദർഘാസ് സ്ഥിരപ്പെടുത്തിയാൽ ദർഘാസ് തുകയുടെ 5% തുക സെക്യൂരിറ്റി ഡെപ്പോസിറ്റായി നൽകേണ്ടതാണ്. യാതൊരു കാരണവും പറയാതെ ഏതെങ്കിലും ദർഘാസോ, എല്ലാ ദർഘാസുകളോ സ്വീകരിക്കുന്നതിനോ, നിരാകരിക്കുന്നതിനോ ഉള്ള



അധികാരം താഴെ ഒപ്പിട്ടിരിക്കുന്ന ആഫീസറിൽ നിക്ഷിപ്തമാണ്. കമ്പ്യൂട്ടർ ലാബ് നെറ്റ്‌വർക്ക് ചെയ്യുന്നതിനുള്ള തുക ദർഘാസിൽ രേഖപ്പെടുത്തേണ്ടതാണ്.

ദർഘാസ് സമർപ്പിക്കുത്തും തുറക്കുന്നതും സംബന്ധിച്ച വിവരങ്ങൾ

ദർഘാസ് നമ്പർ: 1/2023-24

ദർഘാസ് ഫോറം ലഭ്യമാകുന്ന അവസാന തീയതി : 11.03.2024 12 pm

ദർഘാസ് സമർപ്പിക്കുന്നതിനുള്ള അവസാന തീയതി : 11.03.2024 2 pm

ദർഘാസ് തുറക്കുന്ന തീയതി : 11.03.2024 3 pm

ദർഘാസ് വില : Rs.590 (Rs.500+18%GST)

ദർഘാസ് ഫോറം നൽകുന്നതും സ്വീകരിക്കുന്നതുമായ ഉദ്യോഗസ്ഥന്റെ ഔദ്യോഗിക വിലാസം

പ്രിൻസിപ്പാൾ

ശ്രീ. സി അച്യുത മേനോൻ ഗവ. കോളേജ്,

കുട്ടനെല്ലൂർ പി.ഒ. തൃശ്ശൂർ -680014

ഒപ്പ്
പ്രിൻസിപ്പാൾ



TENDER NOTICE

Number: A3/856/2023/CSMGCCLKDY

Date: 21.02.2024

Sealed Tenders are invited for the work of Networking of computer lab (Dept of Statistics) for Rs 2,10,500/- (Two Lakhs Ten Thousand Five Hundred only).

The Tender should be superscribed “Tender No. and Work of Computer lab networking ” and addressed to “The Principal, Sri C Achutha Menon Govt. College, Thrissur-680014”. The filled in tenders should reach this office on or before 11.03.2024 at 12 P.M. Late tenders will not be considered under any circumstances. The tenders will be opened at 3 P.M on 11.03.2024 in the presence of the Tenderers or their authorized representatives who may be present at that time.

Intending tenderers may apply to “Sri C Achutha Menon Govt. College, Thrissur 680014” to obtain the requisite tender form on which tenders should be submitted. Application for tender form should be accompanied by Online payment or Cash remittance of Rs.590/- [500 + 18% GST)] (Rupees Five Hundred and Ninety only) which is the price fixed for a form and which is not refundable. Tender forms are not transferable.

Sale of tender forms will be closed at 12 Noon on 11.03.2024. Cheque, Postage stamps, Demand Draft, Postal Order etc. will not be accepted towards the cost of tender form and not by V.P.P. Duplicate tender forms if required will be issued for Rs.590/- (500 + 18% GST) per copy. For more details visit our website <https://govtcollegethrissur.ac.in/>

Details of works is given below

Sl.No.	Item Description	Quantity
1	Network	
1.01	Managable switch 48 port Gigabit -Supply, installation, fluke testing and commissioning of 1U high, 48-port Gigabit switch maximizes bandwidth and density for great value and capability. With 48 10/100/1000 Mbps ports, each capable of powering 2000 Mbps of data throughout in full-duplex mode, plus four optional fiber ports, it provides a 40 Gbps backbone and connects servers or power users, delivering large amounts of multimedia, image and video information in no time at all. Standards-based, it is ideal for combining 10, 100, and 1000 Mbps devices, as it delivers automatic speed and full/half-duplex sensing plus Auto Uplink™ on every port. Four hot-swappable Small Form-factor Pluggable (SFP)** GBIC slots provide	1 Nos



	optional fiber connectivity for greater distance. An intuitive, web-browser interface offers simple switch management, making it a snap to monitor switch performance, configure ports, even set up trunks, VLANs, and prioritization.	
1.02	Information Outlet RJ 45 - Supply, fixing, fluke testing and commissioning of CAT 6 Information Outlets (Key stone) with Shuttered Faceplate, Single port, white, jack, suitable PVC / GI Modular Box etc. including necessary connections with all accessories required for complete installation.	36 Nos
1.03	CAT6 Cable - Supplying and drawing of Category 6 cable consists of 4 pairs of solid insulated copper 23AWG, surface/ recessed PVC conduit through wall/tray with all accessories as required for complete installation and making good all damages made for installation.	600 Mtrs
1.04	OFC Cable - Supplying and drawing of 6 core un-armoured Optical Fibre Cable (OFC) through wall/tray with all accessories as required for complete installation(From main block BBA lab to Science Block, Approximately 400Mtrs , Through Underground)	400 Mtrs
1.05	Patch cable - Supply, fixing, testing and commissioning of CAT6 Patch Cable - 1 Meter length etc. of approved make as required for complete installation.	36 Nos
2	Active Components, Racks & Accessories	
2.01	Supply, Installation, Testing and installation of Cat - 6, 24 port fully loaded patch panel with necessary cable manager for routing the cable inside rack with all accessories required for complete installation as required as directed by the engineer in charge	2 Nos
2.02	Cable manager	4 Nos
2.03	9U Rack	1 Nos
3	Installation Testing & Commissioning	
3.01	Installation, Testing & Commissioning charges, if any	1 Nos

Sri C Achutha Menon Govt College, Thrissur

Signed by
Principal